



We bring our clients' stories to life.

SPOKANE

203 N. Washington
Ste. 400
Spokane, WA
99201
P 509.838.8568

alscarchitects.com

**Tri-Cities Readiness Center
Request for Proposals (RFP)
Addendum No. 02
July 09, 2020**

I. Request for Proposals

1. See attached Response to Questions for clarifications that do not change RFP documents.
2. Part IV. Design Program Requirements
7.0 B. 11: Change first sentence to read: Provide asphalt concrete pavement for personal vehicle (POV) parking area and roadways.
Change the last sentence to read: Cement concrete is required in repair areas.
3. Part IV. Design Program Requirements
8. OC, Photovoltaic System Ready Roof Structure
Change to read as follows: Provide an area of the roof structure capable of supporting a 100 KVA fixed photovoltaic panel array.
4. Part IV. Design Program Requirements
8.0 C., Snow Loads: Change to read as follows: Flat roof snow load 20 psf (ground snow load 15 psf.)
5. Part V. 3.0 General Site and Site Security A.I.B.
Change to read: Military equipment parking 950 square yards (with area available for up to 50% future expansion.)
6. Part V. 3.0 General Site and Site Security
A. Add: 3. Rigid pavement other than parking 1,329 square yards.
(See Appendix I.C DD – 1390 Area, for breakdown of Rigid Pavement Area)